

TASK ORDER

This Task Order pertains to an Agreement by and between the South Washington Watershed District, (SWWD; "OWNER"), and Houston Engineering, Inc., ("ENGINEER"), dated December 11, 2012, ("the Agreement"). Engineer shall perform services on the project described below as provided herein and in the Agreement. This Task Order shall not be binding until it has been properly signed by both parties or a representative of the Owner provides written authorization to proceed. Upon execution, this Task Order shall supplement the Agreement as it pertains to the project described below.

TASK ORDER NUMBER: 2022-002 PROJECT NAME: Trout Brook Phase 3 – Task 2

PART 1.0 PROJECT DESCRIPTION:

The purpose of this task order is to provide engineering services for the 90% and 100% design drawings, bidding, construction management, and construction observation and staking of stabilization practices and culvert installation.

The Project is located on Vail properties at the Afton Alps Ski Area and on MnDNR Property. See **Attachment A.** The MnDNR has specified goals for improving Trout Brook including; increased longitudinal connectivity from the mouth to the crossing at St. Croix trail South, improved water quality and increased floodplain connectivity in Trout Brook, increased in-stream habitat to improve biological communities in Trout Brook, and increased recreational opportunities for state park users and the public in general.

Phases 1 and 2 of the Project have been completed through partnerships with Great River Greening (GRG), SWWD, the MnDNR and Vail Properties. Previous phases were designed by Inter-Fluve, Inc.

Task 1 of Phase 3 included developing designs for SWWD and project stakeholders to create 30% and 60% preliminary drawings that achieve the project goals for work areas 1, 2, 3, and 4. Task 1 also included regulatory coordination. Partners involved in Phase 3 of the Project are SWWD, GRG, MnDNR, and Vail Properties.

This scope includes: 90% and final plans and specifications, as well as assistance with bidding, construction management, and construction observation and staking.

PART 2.0 SCOPE OF SERVICES TO BE PERFORMED BY ENGINEER:

The Engineer will complete the following tasks for Phase 3 of the Project during execution of this Task Order.

See Attachment B for detailed tasks and associated costs.

Task 2.1: Final Construction Documents 180 Work completed under this task will include: • HEI will build upon the previously developed 60% design plan sheets to develop 90% plans. The plans are assumed to include a coversheet (1), a site access and staging sheet (1), plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert details (1), planting and final stabilization (4), and a SWPPP (1). • • Specification will be developed for the 90% design plans. • • If necessary, HEI will update the HEC-RAS model to the 90% and 100% design features and evaluate impacts to water surface elevations, shear stress, and velocity. • HEI will update the basis of design memo, which will include design assumptions, estimate opinion of probable construction costs, and project impacts. • The draft plans and basis of design memo will be provided to stakeholders and HEI will lead a virtual meeting will project stakeholders and distribute meeting notes. HEI will prepare an agenda in advance of the meeting. • Comments from the stakeholder meeting will be used to provide revised 100% plans and specifications and a revised 100% basis of design memorandum. Final drawings will be signed by a licensed professional engineer. • Assumptions: • The stakeholder meeting will not have a prepared presentation. Comment will be solicited via discussion. • • Stakeholder meeting will not ha	ed Estimated Cost
 H^EI will build upon the previously developed 60% design plan sheets to develop 90% plans. The plans are assumed to include a coversheet (1), a site access and staging sheet (1), plan and profile sheets (7), typical cross section sheets (6), detail sheets (5), box culvert general plan (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical section (1), box culvert plan and profile (1), box culvert typical cost plan (1), box culvert plan and profile (1), box culvert typical cost plan (1), box culvert typical cost plan (1), box culvert plan and profile (1), box culvert details (1), planting and final stabilization (4), and a SWPPP (1). Specification will be developed for the 90% design plans. I the draft plans and basis of design memo, which will include design assumptions, estimate opinion of probable construction costs, and project timpacts. The draft plans and basis of design memo will be provided to stakeholders and distribute meeting notes. HEI will prepare an agenda in advance of the meeting. Comments from the stakeholder meeting will be used to provide revised 100% plans and specifications and a revised 100% basis of design memorandum. Final drawings will be signed by a licensed professional engineer. Assumptions: The plan set will be 29 pages as described above. The stakehold	\$27,800
develop 90% plans. The plans are assumed to include a coversheet (1), a site access and staging sheet (1), plan and profile sheets (7), typical cross section sheets (6), detail sheets (5), box culvert general plan (1), box culvert typical section (1), box culvert plan and profile (1), box culvert details (1), planting and final stabilization (4), and a SWPPP (1). • Specification will be developed for the 90% design plans. • If necessary, HEI will update the HEC-RAS model to the 90% and 100% design features and evaluate impacts to water surface elevations, shear stress, and velocity. • HEI will update the basis of design memo, which will include design assumptions, estimate opinion of probable construction costs, and project impacts. • The draft plans and basis of design memo will be provided to stakeholders and HEI will update the stakeholder meeting will be used to provide revised 100% plans and specifications and a revised 100% basis of design memorandum. Final drawings will be signed by a licensed professional engineer. Assumptions: • The plan set will be 29 pages as described above. • The plan set will be 29 pages as described above. • The stakeholder meeting will not have a prepared presentation. Comment will be solicited via discussion. • Stakeholders will respond to a meeting request in a timely manner. • One unified set of comments will be provided from project stakeholders. • MnDOT's Standard Specifications for Construction, 2020 Edition and any applicable Special Provisions (
will be solicited via discussion.Stakeholders will respond to a meeting request in a timely manner.One unified set of comments will be provided from project stakeholders.MnDOT's Standard Specifications for Construction, 2020 Edition and any applicable Special Provisions (Division S) shall be utilized.Culvert plans will be provided in accordance with the standard MnDOT format regarding details, sheets, plan information organization, etc.Deliverables:Draft 90% design plan set and specificationsDraft 90% Basis of Design MemorandumStakeholder meeting agenda, facilitation, and notes.Revised 100% design plan set and specificationsRevised Basis of Design MemorandumTask 2.2: Bidding ServicesMork completed under this task will include:HEI will solicit public bids for project construction using construction plans and specifications (bid package). The online bidding service QuestCDN	
Deliverables: • Draft 90% design plan set and specifications • Draft 90% Basis of Design Memorandum • Stakeholder meeting agenda, facilitation, and notes. • Revised 100% design plan set and specifications Revised Basis of Design Memorandum Task 2.2: Bidding Services 31 Work completed under this task will include: • HEI will solicit public bids for project construction using construction plans and specifications (bid package). The online bidding service QuestCDN	
 Draft 90% design plan set and specifications Draft 90% Basis of Design Memorandum Stakeholder meeting agenda, facilitation, and notes. Revised 100% design plan set and specifications Revised Basis of Design Memorandum Task 2.2: Bidding Services 31 Work completed under this task will include: HEI will solicit public bids for project construction using construction plans and specifications (bid package). The online bidding service QuestCDN 	
 Work completed under this task will include: HEI will solicit public bids for project construction using construction plans and specifications (bid package). The online bidding service QuestCDN 	
HEI will solicit public bids for project construction using construction plans and specifications (bid package). The online bidding service QuestCDN	\$5,700
 Virtual bidding will be set up and coordinated on QuestCDN vBid, and a bid opening meeting will be conducted on a virtual platform. HEI will address contractor questions that arise during the bidding process which may be addressed with one bid addenda. A pre-bid meeting will be held on-site to explain the project and items of concern to potential bidders. A bid abstract will be prepared, tabulating the bids received, and a 	

Tasks	Estimated Hours	Estimated Cost
Assumptions:		
1. One solicitation of bids		
2. A total of 8 hours was assumed for addressing bidder questions and		
issuing 1 addendum.		
3. One onsite pre-bid meeting.		
A virtual bid opening meeting.		
5. SWWD will post bid advertisement within Pioneer Press or local		
newspaper.		
Deliverables:		
1. Pre-Bid meeting; agenda facilitation, and notes		
2. Up to 1 addendum		
Bid tabulation memorandum	01	<i></i>
Task 2.3: Construction Management Services	91	\$16,300
Work completed under this task will include:		
HEI will prepare a Notice of Award for the board approved bidder and soundination with the selected contractor to obtain processory contract		
coordination with the selected contractor to obtain necessary contract documents. HEI will review and approve the documents. After Board		
approval to proceed with the project, HEI will prepare the Notice to Proceed for the contractor.		
 HEI will process technical submittals (shop drawings, material testing, etc.) 		
that will be required by the contract before and during construction.		
 Prior to construction activity, HEI will hold a pre-construction meeting on-site 		
with the project partners, and the contractor. We will prepare a pre-		
construction meeting agenda and minutes following the meeting.		
 During construction, HEI will review payment applications, issue field orders, 		
and change orders, to the contractor.		
 HEI will be responsible for reviewing pay applications and providing a 		
recommendation letter and payment summary to SWWD.		
Assumptions:		
Review of no more than four (4) technical submittals.		
One onsite pre-construction meeting.		
 Processing four (4) payment requests, two (2) field orders, and two (2) 		
change orders.		
 2.5 hours per week of phone-call coordination with SWWD staff 		
Deliverables:		
Recommendation of Award, Notice of Award, Notice to Proceed		
 Review of contractor submittals (shop drawings) 		
 Payment Recommendations (4) 		
• Field orders (2) and change orders (2)		
Task 2.4: Staking, Observation, and Record Drawings	399	\$68,500
Work completed under this task will include:		
HEI will provide technical assistance and construction observation during		
significant construction activities. HEI will provide construction observation		
for 26 days on site (excluding construction meetings, averaging six hours per		
day on-site. If additional construction observation time is desired (due to		
prolonged construction or other factors), additional fees will be incurred.		
HEI's construction observation will include site visits during of the		
construction period to verify construction is completed per plans and the bid		
package. Project communication during the entire construction period will be		
coordinated by HEI, including immediate communication on urgent issues		
with SWWD.		

Tasks	Estimated Hours	Estimated Cost
 HEI will prepare weekly progress reports that will include a summary of work completed during the week, documentation of problems encountered, summary of work schedule for the next week, and documentation of any changes authorized to the original construction documents. The progress report will also include photos of the work completed during the week. Onsite progress meetings will be held with contractor and project partners on a weekly or bi-weekly basis, depending on pace of construction. Construction staking will be coordinated with the contractor, with the assumption that HEI's survey crew will complete staking in 3 trips. After construction activities are complete, HEI will provide an as-built survey and record drawings to SWWD for your records. Prior to project acceptance and final payment, HEI will conduct a site visit with staff, project partners, and the contractor to create a final punch list of items needing completion prior to closeout. Subsequently, one final 		
inspection will verify the completion of the punch list items prior to final payment. Assumptions:		
 Construction will be completed in a 14-week period. Observation services assume 26 days at 6 hours per day onsite and documentation. 		
 Three trips totaling 32 hours for construction staking. One day trip for as-built survey. Completion of record drawings locating critical site features. 		
 Weekly progress reports will be provided as part of the observation services. Eight (8) on site construction coordination meetings One onsite punch list meeting and one final inspection. 		
 12 weeks of construction will occur in 2022 and 2 weeks in 2023. <u>Deliverables:</u> Weekly observation services and progress reports 		
 Final punch-list Record drawings Task 2 Total (this task order): 	701	\$118,300

PART 3.0 OWNER'S RESPONSIBILITIES:

The estimated compensation for the completion of the tasks identified within *Scope of Services to be performed by Engineer on the Project* is based upon the following assumptions and owner responsibilities:

- 1. The OWNER will be responsible for all assumptions and client obligations as stated.
- 2. OWNER staff shall review and provide all written or oral comments concerning the draft work products in a timely manner allowing sufficient time for incorporation into the final work products:
 - a. 90 % Plans and Specifications
- 3. The OWNER shall be responsible for landowner communication, meetings, and coordination.
- 4. The OWNER shall attend construction meetings and provide timely response to construction contracting items such as payments, change orders, and written questions.

PART 4.0 PERIODS OF SERVICE:

Initiating one or more tasks as described within *Scope of Services to be Performed by Engineer on the Project* occurs at the time of execution of this Task Order or written email notification by the OWNER. Work described within this Task Order shall be completed by December 31, 2023.

Anticipated Schedule for the time of completion of associated tasks:

<u>Task</u> Phase 1		Completion Date
	Task 1.1 -1.6	Complete
	Task 1.7 60% Design Stream Features	February/March, 2022
	Task 1.8 60% Design Bridge	February/March, 2022
	Task 1.9 Regulatory, Permitting, Environmental Coordination	June, 2022
Phase 2		
	Final Plans and Construction Documents	May, 2022
	Bidding/Contractor Contract	May/June, 2022
	Construction Management	July 2022 – Dec 2023


PART 5.0 PAYMENTS TO ENGINEER:


ENGINEER will perform the professional services identified within *Scope of Services to be Performed by Engineer on the Project* on a time and materials basis up to a maximum amount not-to-exceed **\$118,300** (i.e., Total Compensation) for Phase 3 Task 2 of the Project. ENGINEER shall not exceed the Total Compensation during the completion of the tasks described within this Task Order without prior authorization from the OWNER's designated representative. ENGINEER reserves the right to move dollars across tasks, while remaining within/below the Total Compensation identified within this Task Order.


PART 6.0 OTHER:

OWNER's designated representative for this project is Mr. John Loomis. ENGINEER's designated representative for this project is Mr. Greg Bowles. The designated representative is responsible for the technical work executed under this Task Order.

PART 7.0 SIO	GNATURES: AM executed this day of	February,	20 2 7-
South Washingtor "OWNER"	n Watershed District	Houston Engineer	
BY:	S.A.	BY:	Barton O. Schult
NAME:	Brian Johnson	NAME:	Bart Schultz, PE
TITLE:	Board President	TITLE:	Office Manager
ADDRESS:	2302 Tower Dr Woodbury, MN 55105	ADDRESS:	7550 Meridian Cir N, Suite 120 Maple Grove, MN 55369









South Washington Watershed District Frout Brook Phase 3 Location Map												
Scale: AS SHOWN	Drawn by: ESN	Checked b LDO	oy:	Project No.: 4876-0051	Date: 1/28/2022	Sheet: 1						
	Houston Engineer	ing Inc		Maple Grove P: 763.493.452								
	Engineer	ing inc.		F: 763.493.557								

ATTACHMENT B Trout Brook Phase 3 - Task 2

Prepared by: L. Odens

Date prepared: 1-28-2022

2022 Rate \$ 202.00 \$ 184.00 \$ 146.00 \$ 140.00 \$ 175.00 \$ 97.00 \$ 197.00 \$ 0.59 \$ 0.79 \$ 25.00																		
To	otal Hours 11	.9.5	148.5	22.0	22.0	243.0	6.0	34.0	53.0	5.0	48.0	3,710.0	636.0	36.0	701.0			
												Expenses	Expenses					
								Engineer 7			2-Person	Mileage	Mileage	Expenses	Estimated			Estimated Cost
TASK DESCRIPTION	Engir	neer 10	Engineer 8	Engineer 6	Engineer 4	Engineer 3	Technician 10	CAD	CAD Tech II	Scientist 5	Crew	Regular	Survey	GPS	hours	Cost Labor	Expenses	1
Task 2: Final Design and Construction Management	11	19.5	148.5	22.0	22.0	243.0	6.0	34.0	53.0	5.0	48.0	3710.0	636.0	36.0	701.0	114749.0	\$3,570	\$118,319
Task 2.1 90% Design & Plans (Next Phase Stream and Culvert)	1	7.0	30.0	15.0	22.0	20.0	0.0	34.0	37.0	5.0	0.0	0.0	0.0	0.0	180.0	27830	\$0	\$27,830
Cover Sheet									1.0						1.0	97.0	\$0	\$97
Site Access and Staging Sheet			1.0					1.0							2	359.0	\$0	\$359
Plan and Profile			2.0					16.0	12.0						30	4332.0	\$0	\$4,332
Typical Cross Sections			1.0					2.0	2.0						5	728.0	\$0	\$728
Detail Sheets									2.0						2	194.0	\$0	\$194
Structural Sheets	1	1.0		6.0	16.0				12.0						35	4698.0	\$0	\$4,698
Erosion Control Details									1.0						1	97.0	\$0	\$97
SWPPP (2)	1	1.0							1.0						2	299.0	\$0	\$299
Specifications	2	2.0	12.0	6.0	6.0	20.0		4.0							50	7984.0	\$0	\$7,984
QAQC	6	5.0													6	1212.0	\$0	\$1,212
Finalize Design Memorandum (cost estimate, basis of design)	1	1.0	6.0					2.0							9	1656.0	\$0	\$1,656
Address comments from Stakeholders and Permitting (Update design and plans)	1	1.0	2.0					2.0	2.0	2.0					9	1448.0	\$0	\$1,448
100% Final Plans	1	1.0	2.0					4.0	4.0						11	1658.0	\$0	\$1,658
Virtual Stakeholder Meeting (Agenda and Notes)		1.0	1.0	1.0				1.0		1.0					5	894.0	\$0	\$894
General Project Management		1.0	1.0												2	386.0	\$0	\$386
Internal Team Meetings	1	2.0	2.0	2.0				2.0		2.0					10	1788.0	\$0	\$1,788
Task 2.2 Bidding		7.0	21.0	0.0	0.0	3.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	31.0	5698	\$0	\$5,698
Advertisement for Bids by Posting to Quest.CDN			5.0												5.0	920.0	\$0	\$920
Pre Bid Meeting (agenda, meeting, notes)(onsite)		3.0	8.0												11	2078.0	\$0	\$2,078
Bidder Questions / Addendums	2	2.0	6.0												8	1508.0	\$0	\$1,508
Bid Opening (virtual meeting)	1	1.0	1.0												2	386.0	\$0	\$386
Bid tabulation and contractor selection memorandum		1.0	1.0			3.0									5	806.0	\$0	\$806
															0	0.0	\$0	\$0
Task 2.3 Contract Management	2	8.5	40.5	6.0	0.0	12.0	0.0	0.0	4.0	0.0	0.0	0.0	0.0	0.0	91.0	16273	\$0	\$16,273
Contract Documents	1	1.0	4.0												5	938.0	\$0	\$938
Review shop drawings	1	1.0	1.0	6.0											8	1382.0	\$0	\$1,382
2 Change Orders, 2 Field Orders	2	2.0	6.0						4.0						12	1896.0	\$0	\$1,896
Pre-construction meeting (Engineer and Inspector)		3.0	4.0			4.0									11	1902.0	\$0	\$1,902
Processing Pay Requests (4 requests, include progress report)	4	4.0	8.0			8.0									20	3400.0	\$0	\$3,400
Coordination with SWWD during construction (30 minutes per day for 14 weeks)	1	7.5	17.5												35	6755.0	\$0	\$6,755
		-	-												0	0.0	\$0	\$0
Task 2.4 Staking and Inspection	6	7.0	57.0	1.0	0.0	208.0	6.0	0.0	12.0	0.0	48.0	3710.0	636.0	36.0	399.0	64948	\$3,535	\$68,483
Staking (assume 3 days of survey)		2.0					4.0				32.0		424.0	24.0	38	7388.0	\$922	\$8,310
Part-Time Construction Observation (26 days on site; assuming 6 hours on-site + 2 hours		0.0	20.0		1	208.0	-	1		1	-	2756.0		-	248	36840.0	\$1.598	\$38.438
Weekly construction meetings (8 meetings, 6 hours on-site + 2 hours driving)	0.	6.0	36.0		1		1				1	848.0			72	13896.0	\$492	\$14,388
Punch list site visit		3.0			1	1	1	1	1	1	ł	106.0	1	1	8	1616.0	\$61	\$1,677
As-built Survey				1	1	1	2.0	1	1	1	16.0		212.0	12.0	18	3492.0	\$461	\$3,953
Record Drawings		1.0	1.0	1.0		1	2.0		12.0		10.0				15	1716.0	\$0	\$1,716
			1.0	1.0	+	+	+	1	12.0	+	+	1	+	1	- 15	0.0	\$0 \$0	\$1,710